



Standard Test Method for Measuring Consistency of Self-Flowing Castable Refractories¹

This standard is issued under the fixed designation C1446; the number immediately following the designation indicates the year of original adoption or, in the case of revision, the year of last revision. A number in parentheses indicates the year of last reapproval. A superscript epsilon (ϵ) indicates an editorial change since the last revision or reapproval.

1. Scope

1.1 This test method covers the determination of the consistency (degree of self-flow) and working time of self-flowing castable refractories. This test may optionally be used to determine working time of self-flowing castables.

1.2 The values stated in inch-pound units are to be regarded as the standard. The values given in parentheses are for information only.

1.3 *This standard does not purport to address all of the safety concerns, if any, associated with its use. It is the responsibility of the user of this standard to establish appropriate safety and health practices and determine the applicability of regulatory limitations prior to use.*

2. Referenced Documents

2.1 *ASTM Standards:*²

C71 Terminology Relating to Refractories

C230/C230M Specification for Flow Table for Use in Tests of Hydraulic Cement

C860 Test Method for Determining the Consistency of Refractory Castable Using the Ball-In-Hand Test

C862 Practice for Preparing Refractory Concrete Specimens by Casting

C1445 Test Method for Measuring Consistency of Castable Refractory Using a Flow Table

E177 Practice for Use of the Terms Precision and Bias in ASTM Test Methods

E691 Practice for Conducting an Interlaboratory Study to Determine the Precision of a Test Method

3. Terminology

3.1 *Definitions of Terms Specific to This Standard:*

¹ This test method is under the jurisdiction of ASTM Committee C08 on Refractories and is the direct responsibility of Subcommittee C08.09 on Monolithics.

Current edition approved July 1, 2011. Published August 2011. Originally approved in 1999. Previous edition approved in 2007 as C1446 – 07. DOI: 10.1520/C1446-11.

² For referenced ASTM standards, visit the ASTM website, www.astm.org, or contact ASTM Customer Service at service@astm.org. For *Annual Book of ASTM Standards* volume information, refer to the standard's Document Summary page on the ASTM website.

3.1.1 *consistency of self-flowing castable refractories*—the degree of mobility (self-flow) of the refractory castable under its own weight as described in this test method at the specified times after adding liquid to the mixer.

3.1.2 *working time of self-flowing castable refractories*—the elapsed time from the first addition of liquid during mixing until the mix will only achieve 25 % self-flow using the procedure described in this test method.

4. Summary of Test Method

4.1 The castable refractory is mixed with a tempering liquid and the percentage of self-flow is measured. Self-flow is the percent increase in the diameter of the sample after removing the Specification C230/C230M cone mold and allowing the specimen to flow (spread) under its own weight for 120 s. The consistency is measured 10 min after water addition. Working time may optionally be determined by repeating the self flow test at regular time intervals.

5. Significance and Use

5.1 This test method is used to measure the consistency (degree of self-flow) that a castable refractory demonstrates at a given level of tempering liquid at specified time intervals after the liquid is added. A self-flow of 25 % has been selected as the minimum at which a mix can be poured into typical molds or forms in normal practice.

5.2 Castable refractories which are self-flowing at one level of tempering liquid will require vibration for placement at some lower level of tempering liquid. At the tempering liquid levels which require vibration or tamping for placement, the castable refractory should be characterized using test methods which are appropriate for castable refractories designed for vibration placement, such as Test Method C1445.

5.3 This test method is not appropriate for determining the pumpability of castable refractories.

6. Interferences (Factors Known to Affect Results)

6.1 During method development, a ruggedness evaluation was performed using a castable comprised of 5 % cement, 17 % reactive alumina, and 78 % tabular alumina. Several